	Particulars	Unit	Quantity	Rate
	of testing the pipe line before the closing of the trench for pipes of sizes as in following :—			Rs. a. p.
	7" diameter	R.ft.	889	
	6" "	"	2,023	
	4" "	"	340	
	The pipe line will be kept open for the inspection of each joint by the Executive Sanitary Engineer or his representative and will not be closed without his permission.	..	..	
III.	Constructing manholes of 4 ft. diameter including earthwork, excavation, correct to the required dimension, cement concrete bed of one foot depth and 6¾ ft. diameter, side walls of 1½ foot thick of wire-cut brick in cement mortar 1 to 5, if necessary taper for fixing the manhole frame including the cost of cast iron manhole cover and frame of 2 cwt. and of design to be seen at the office and necessary number of cast iron steps of the standard design, making drains with cement concrete and cement plaster, ¾ of the depth of the pipe drain joining it and with 4" slope from side walls to drain and cement plastering ½" thick inside the manhole all over with 1 to 3 cement mortar, etc., complete of depths as in the following :—			
	Upto 2 feet depth	No.	3	
	2' to 3' depth	"	3	
	3' to 4' "	"	4	
	4' to 5' "	"	4	
	5' to 6' "	"	1	
	6' to 7' "	"	1	
	7' to 8' "	"	1	
	8' to 9' "	"	1	
IV.	Providing house connections including the cost of 6" x 4" stoneware gully trap with cast iron grating and 4" diameter stoneware pipes and junction pipes on sub-main line, if necessary, and constructing cisterns with cast iron hinged lid and frame of 14" x 10" complete ..	"	5	
V.	Constructing ventilating shafts with 4" boiler tube of 16 ft. height, masonry support including cement plastering to it and cost of cast iron bend and pipes up to manhole and fixing complete	"	1	

B. R. GARUDACHAR,
Executive Sanitary Engineer

MYSORE RAILWAYS.

Dated 20th June 1933.

TENDERS FOR THE CONTRACT OF INDIAN REFRESHMEMT ROOM ATTACHED TO RAILWAY CENTRAL OFFICES AT MYSORE.

Tenders are invited till 15th July 1933 for running the above Refreshment Room for the convenience of the Staff from 1st July 1933 to 30th June 1935.

The tenderer should clearly specify the amount that he is prepared to pay for the right and also the rate at which the different items of refreshments, etc., will be sold. The tender should be accompanied by an earnest money of Rs. 25 in cash or currency notes. The earnest money will be returned to the unsuccessful tenderer and detained in the case of successful tenderer as earnest, till the end of contract.

The tenders sealed and superscribed " Tenders for Indian Refreshment Room at Mysore Railway Central Offices," should be sent so as to reach the undersigned on the 15th July 1933 at 2 P.M.

The Railway Administration do not bind themselves to accept the highest or any tender or assign any reason for rejecting the tender.

The successful tenderer must pay the amount of contract within seven days of acceptance of the contract and execute an agreement failing which the right will be resold at his risk.

The successful tenderer must be ready to accept any fine or penalty that the Executive Engineer, Mysore Railways, may impose upon him for selling any preparation or exhibition thereof in the Refreshment Room which may be considered to be injurious to [illegible]